



# PROJECT MANAGEMENT DIVISION

2015 Nevada Transportation Conference

Cole Mortensen, PE Asst. Chief of Project Management

#### **PM Division Responsibilities**

- > FHWA Major Projects
  - Total project cost > \$100 Million
    - FHWA Project Management Plan & Finance Plan
- ➤ NDOT's Major Capacity Improvement Projects (typically > \$25 million)
- Pioneer Program
  - Innovative Project Delivery (CMAR, DB, DBF)
  - Unsolicited Proposals





#### Exhibit 6 – Major Types of Public-Private Partnerships

**Asset Sale** 

**Full Service Long-Term Concession or Lease** 

Multimodal Agreement (Public-Public Partnership)

Joint Development Agreement (JDA - pre-development)

Transit-Oriented Development (TOD - post-development)

**Build-Own-Operate (BOO)** 

**Build-Own-Operate-Transfer (BOOT)** 

**Build-Transfer-Operate (BTO)** 

**Build-Operate-Transfer (BOT)** 

Design-Build-Finance-Operate (DBFO)

Design-Build-Operate-Maintain (DBOM)

Design-Build with Warranty (DB-W)

Design-Build (DB)

Construction Manager at Risk (CM@Risk)

Contract Maintenance

Fee-Based Contract Services

High

**Alternative** 

Project Delivery

Approaches

Degree of Private Sector Responsibility and Risk

Low













#### **FHWA Major Projects - Clark**









## FHWA Major Projects - Washoe



# Risk Management, Cost Risk Analysis, Finance Plan and PMP










#### **Major Projects Cost Trend**







#### **Cost / Risk Management**

- Redesign of base concept 2007
- NEON VA Study October 2008
- CRA #1 December 2008
- > CRA #2 October 2010
- Scoping Workshop November 2010
- Phase 1 CRA March 2011
- > TAC Workshop August 2011
- MLK+I VA Study November 2011
- Every Day Counts December2011

- > ABC Workshop March 2012
- Every Day Counts September 2012
- Risk Allocation Workshop June2013
- > R/W CRA September 2013
- > 2013 ICE October 2013
- > R/W CRA –January 2014
- Future Phase CRA February 2014
- Construction CRA April 2014
- CRA update February 2015













#### **US 95 NW**







## **Boulder City Bypass**







#### **Project NEON**

➤ HOV System: Adding Lanes and Connectors to Link HOV Lanes on US 95 and I-15









## PROJECT LOCATION

#### Projects:

- 1) I-15 South Sloan Road Interchange
- 2) I-15 South Bermuda Road Interchange
- 3) I-15 South Starr Avenue Interchange
- 4) I-15 South Cactus Avenue Interchange
- 5) I-15 South Pebble Road Overpass
- 6) I-15 South Freeway Improvements (Phase 1A):

From Blue Diamond Road to Tropicana Avenue

- 7) I-15 South Phase 1B: From Blue Diamond Road to Tropicana Avenue
- 9) I-15 South Phase 2B: From Sloan Road to Tropicana Avenue
- 10) I-15 South Las Vegas Boulevard-Two packages:


Package 1: From Silverado Ranch Boulevard to Sunset Road

Package 2: From St. Rose Parkway to Silverado Ranch Boulevard.










#### **NDOT Major Projects**







#### I-15 North





I-15/I-215 Interchange






### SR 160 - Project Limits



#### **Tropicana Interchange**










### **NDOT Major Projects**









## Near Term HOV System – Major element of US 95, NEON, Gap, I-15 South



### **Long Term HOV System**




### **NDOT Major Projects**







#### **USA Parkway**






- Transportation Link from I-80 (Storey County) to US 50 (Lyon County)
- > 5.5 Miles Existing Paved Road
- ➤ 4.4 Miles Existing Graded Road
- 8.5 Miles of New Roadway





### **Major Projects - Washoe**







#### **Other Projects**

#### **Active**

- Boulder City Phase II DB
- Mesquite DB
- Tropicana ADA
- Tropicana Escalators
- Verdi Bridges Bridge Scour
- Airport Connector
- McCarran/Pyramid Intersection
- Regional Traffic Modeling
- 515 Stephanie
- > 515 Horizon
- US-50 Bypass


#### **Somewhat Active**

- Ivanpah Airport
- Desert Xpress
- Wadsworth Bypass
- Geiger Grade Realignment
- Sheep Mountain Pkwy





### **Clark Projects**















#### NDOT Pioneer Program Guidelines


- Provides a framework, general process, and structure for the implementation of DB and CMAR contracts
  - Procurement process
  - Design process
  - Contract administration process







#### **Procurement Process**



- Design Build (NRS 408):
  - Two Step procurement process:
    - RFQ and RFP
  - Qualification selection is based on designer, contractor and subs experience and qualifications (establish a short list of qualified DB teams)
  - Short listed firms submit proposals
  - Award on Best Value basis
    - Combination of price, technical concepts and schedule


- CMAR (NRS 338)
  - One step procurement process:
    - RFP
  - Contractors submit proposals
  - Award is (typically) based on Contractor's past experience and qualifications (NDOT may hire ICE and Designer through separate procurement process)
  - Award of pre-construction services based on qualifications
  - Award of construction contract based on GMP





# Contract Administration – DB Design Process

- NDOT defines minimum standards for design and construction
- Contractor(s) identify innovation through ATC process
- the design-builder assumes responsibility for the final design work
- NDOT reviews and approves design submittals








# Contract Administration CMAR (CMGC) Design Process

- CMAR assist the NDOT and Design Service Provider in the design of a Project during preconstruction
  - Identifies construction innovation
  - Design and construction risks are identified and quantified








#### **Risk Allocation**


- Risk allocation is an essential element of innovative delivery projects (DB, CMAR and DBFOM)
- Innovative delivery provides flexibility in risk allocation Keeping, sharing or transferring risks that traditionally are borne by NDOT








#### Risk Distribution – DB & CMAR







## **DB Projects**







#### **CMAR Projects**

- > Completed:
  - Moana DDI
  - Tahoe Bike Path
  - Carlin Tunnels
  - Kingsbury Grade
- Design Phase
  - Tropicana Escalators
- > Procurement Process
  - Verdi Bridges
  - Tropicana ADA













## Schedule

Design-Build Project	Time between NEPA Approval and Start of Construction	Time finished ahead of Design-Bid-Build Schedule
I-15 North	6 months	1 year
I-15 South	7 months	1.5 years
I-80	6 months	6 months
Mesquite	1 month	6 months
I-15 ITS	1 month	9 months





# Innovation

Design-Build Project	Total ATCs	ATCs Used	Example Innovation
I-15 North	27	5	Lake Mead Interchange Traffic Management
I-15 South	37	14	Blue Diamond Fly-Over In-Place Bridge Construction
I-80	67	10	Traffic Management Auxiliary Lanes ITS/Ramp Meters
Mesquite	30	4	Accelerated Bridge Construction (ABC)
I-15 ITS	10	1	Combination of Wireless & Fiber Solutions











## **Program Performance - Innovation**

Specific 1		(G)	The same	Tollar Falls		
<b>Innovation Performa</b>	nce					
P roject	C ons truct	ion C os t	Estimated Direc	ct S avings <sup>1</sup>		
Moana DDI	\$	6,978,978.00	\$ 1,544,498			
Tahoe Bike Path	\$	1,424,013.00	\$	275,000.00		
Carlin Tunnels	\$	31,158,944.13	\$ 2,790,000.00			
Kings bury Grade	\$	14,877,619.20	\$ 7,345,000.0			
Tropicana Escalators		TBD		TBD		
Total	\$	54,439,554.33	\$	11,954,498.00		
	21.96%					

1 – Based on proposed innovations and savings recognized during design





## **Program Performance - Schedule**

Schedule Performan	ce. Design and Con			D.D.	D. Catharatad Ca	مارياه مارا			<u> </u>
_		C MAR S chedule		UB	B Estimated Sc	% Time Savings <sup>2</sup>			
	Design <sup>1</sup>	C onstruction	Total	Design <sup>1</sup>	Construction	Total	Design <sup>1</sup>	Construction	Total
Moana DDI	5 months	3 months	8 months	8 months	8 months	16 months	37.5%	62.5%	50.0%
Tahoe Bike Path	6 months	2 months	8 months	8 months	9 months	17 months	25.0%	77.8%	52.9%
Carlin Tunnels	5 months	16 months	21 months	8 months	24 months	32 months	37.5%	33.3%	34.49
Kingsbury Grade	8 months	7 months	15 months	8 months	29 months	37 months	0.0%	75.9%	59.5%
Tropicana Escalators				18 months	18 months	36 months			








## Program Performance – Final Bid Prices

Final Bid	CMAR Contractor's Bid	Independent C os t E s timate (IC E)		Engineer's Cost % Diff. between 9 Estimate (EE) Bid/ICE		% Diff between Bid/E E
Moana DDI	\$ 6,978,978.00	\$	6,921,047.31	\$ 6,962,832.29	0.83%	0.23%
Tahoe Bike Path	\$ 1,424,013.00	\$	1,470,128.18	\$ 1,520,491.14	-3.24%	-6.78%
Carlin Tunnels	\$ 31,158,944.13	\$	31,276,349.29	\$ 28,606,559.54	-0.38%	8.19%
Kings bury Grade	\$ 14,877,619.20	\$	14,830,500.57	\$ 14,101,765.99	0.32%	5.21%
Tropicana Escalators	TBD		TBD	TBD		





### **CMAR Process**







## **Pre-Construction Costs**

4/10	reg l	1					Pro	
Cost Performance:	Preco	onstruction Cos	t					
							CMAR Fee as %	ICE Fee as %
	CN	AR Design Fee	IC	E Services Fee	Со	ns truction C os t <sup>1</sup>	of Const. Cost	of Const. Cost
Moana DDI	\$	335,160.49	\$	193,100.00	\$	6,978,978.00	4.80%	2.77%
Tahoe Bike Path	\$	97,457.91	\$	120,704.70	\$	1,424,013.00	6.84%	8.48%
Carlin Tunnels	\$	265,500.00	\$	271,700.00	\$	31,158,944.13	0.85%	0.87%
Kings bury Grade	\$	237,750.00	\$	123,946.09	\$	14,877,619.20	1.60%	0.83%
Tropicana Escalators		TBD		TBD		TBD	TBD	TBD
Total	\$	935,868.40	\$	709,450.79	\$	54,439,554.33	1.72%	1.30%
1 = Cost includes Risk Reserve expeditures								






# Program Performance - Risk

			R is k R	oc on	IΑ	R is k R es	DBB Contingency <sup>1</sup>	
Drojecto	Construction Cost		Proposed	CJCII	Applied	Proposed	Applied	DDD Containgency
Projects	Construction Cost	<u> </u>	'		11	•	- ''	E 000/
Moana DDI	\$ 6,978,978.00	\$	280,000.00	\$	227,230.52	4.01%	3.26%	5.00%
Tahoe Bike Path	\$ 1,424,013.00	\$	66,000.00	\$	4,030.00	4.63%	0.28%	7.00%
Carlin Tunnels	\$ 31,158,944.13	\$	630,000.00	\$	374,808.97	2.02%	1.20%	3.00%
Kings bury Grade	\$ 14,877,619.20	\$	1,850,000.00	\$	250,000.00	12.43%	1.68%	5.00%
Tropicana Escalators	TBC		TBD		TBD	TBD	TBD	
Total	\$54,439,554.33	\$	2,826,000.00	\$	856,069.49	5.19%	1.57%	


1 – NDOT Project Estimation Manual, Oct. 2012








### **CMAR Process**








### **DB Process**







### **DB Process**







### **CMAR Process**

